

ER-5-3831

[Redacted]

25X1A6d

16 March 1954

MEMORANDUM

TO : Acting Deputy Director / Administration

FROM : [Redacted]

25X1A6d

SUBJECT : Parking Lot and Access Road / [Redacted]

25X1A

25X1A

1. Authority is requested for the expenditure of approximately \$15,250.00 for the construction of an access road and automobile parking area [Redacted]. This parking area will be needed to provide automobile parking for vehicles of employees and students and to provide increased parking facilities in case of an emergency. 25X1A6d

25X1A6d

2. The estimate prepared by the Engineering Division at the [Redacted] was \$13,646.60. The Real Estate and Construction Division, Logistics Office, increased the figure to \$15,250.00, because of the rock formation generally found throughout the area. The funds are available in the [Redacted] Budget. 25X1A6d

3. The parking area would be 117' x 250' and would accommodate 103 automobiles. The access road would be approximately 370' long. The road would be 18' wide, including shoulders, 12' of which would be paved. A breakdown of the estimated costs is attached.

*VOID*

[Redacted]

25X1A9a

APPROVED: *19 March 1954*

*[Signature]*  
L. K. WHITE  
Acting Deputy Director / Administration

FOIAb3b

~~CONFIDENTIAL~~

PROPOSED PARKING AREA AND ACCESS ROAD

ACCESS ROAD

|   |              |
|---|--------------|
| Excavation (Bulldozer)<br>400 cu. yds. @ .50  | \$ 200.00    |
| Base - 2-4" compacted layers of<br>crushed stone or gravel<br>738 sq. yds. @ \$1.85 | 1360.00      |
| Surface 1/2" Class A Surface<br>Treatment Designation AT-50<br>492 sq. yds. @ .40   | 197.00       |
| Culverts<br>40' of 18" corrugated iron @ \$5.00<br>per lineal ft. in place          | 200.00       |
| Seeding<br>2220 sq. ft. @ \$14 per 1,000 sq. ft.                                    | <u>31.00</u> |
| TOTAL ESTIMATE FOR ACCESS ROAD  | \$1,988.00   |

PARKING AREA

|  |                    |
|--|--------------------|
| Excavation (including stockpiling<br>topsoil)<br>8264 cu. yds. @ .30 | \$2480.00          |
| Pavement<br>3250 sq. yds. @ \$2.25                                   | 7313.00            |
| Drainage Ditch<br>737 lineal feet @ .50                              | 369.00             |
| Painting Lines<br>3408 lineal feet @ .075                            | <u>256.00</u>      |
| TOTAL ESTIMATE FOR PARKING AREA                                      | <u>\$10,418.00</u> |

|                      |                 |
|----------------------|-----------------|
| GRAND TOTAL          | \$12,406.00     |
| Plus 10% Contingency | <u>1,240.60</u> |
|                      | \$13,646.60     |

RECAP

|   |                 |
|---|-----------------|
| Parking Area (117' X 250')                                  | \$10,418.00     |
| Access Road (370' long x 12' wide)                          | 1,988.00        |
| Real Estate & Construction (Add. for rock &<br>contingency) | <u>2,844.00</u> |
| TOTAL   | \$15,250.00     |

CONFIDENTIAL