

10 February 1971

Correction to: List of Contractural Defects on Table Ser. No. 001
dated 31 December 1970; item 12 therein


1. To assure that the procedures used were correct, and that the color properties of the light source were as reported, further checking has been accomplished. This checking has shown an omission in the handling of the data which significantly alters the reported values for correlated color temperature and color rendering index.

2. The corrected values are as follows:

	<u>Mean</u>	<u>High</u>	<u>Low</u>
Correlated Color Temp. (K)	4894	4956	4794
Color Rendering Index	72.45	73.38	71.27
X co-ordinate	0.3502	0.3534	0.3483
Y co-ordinate	0.3737	0.3752	0.3720

These readings are taken from a set of 8 data listings, 4 on each format.

3. This table now meets the specifications of Color of Illumination STAT as defined in para. 3.1.1.2 of the technical requirements.



TEST & EVALUATION BRANCH, ESD, TSG

Declass Review by NGA/DoD