
|             |        | ROUTING          |        |            |          |  |
|-------------|--------|------------------|--------|------------|----------|--|
| TO:         | NAME A | AND ADDRESS      | D      | ATE        | INITIALS |  |
| 1           |        |                  |        |            |          |  |
| 2           |        |                  |        |            |          |  |
| 3           |        |                  |        |            |          |  |
| 4           |        |                  |        |            |          |  |
| Λ           | CTION  | DIRECT REPLY     | PREPAR |            | RE REPLY |  |
| APPROVAL    |        | DISPATCH         |        | RECOMMENDA |          |  |
| COMMENT     |        | FILE             |        | RETURN     |          |  |
| CONCURRENCE |        | INFORMATION      |        | SIGNATURE  |          |  |
| REMA        |        | ADDRESS, AND PHO | NE NO  | ).         | DATE     |  |
|             |        |                  |        |            |          |  |
|             |        |                  |        |            | Ì        |  |

|         | SECRE                                     | _ 29      |     |
|---------|---|-----------|-----|
|         | (Security Classification)                 |           |     |
|         |   |           | 25X |
|         |   |           |     |
|         |   |           |     |
|         |   |           |     |
| CONTROL | NO. <u>Z-17249/84</u><br>NPIC/IEG (12/84) | ********* |     |
| COPY    | OF  |           |     |
|         |   |           |     |

Warning Notice
Intelligence Sources or Methods Involved
NATIONAL SECURITY INFORMATION
Unauthorized Disclosure Subject to Criminal Sanctions



SECRET
(Security Classification)



| SECRET   |   |  |  |  |  |
|--|---|--|--|--|--|
|  | 25X1  |  |  |  |  |
| (c) NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER  |   |  |  |  |  |
|  |   |  |  |  |  |
| Page 1 of 3 Attachment to Z-   | 17249/84  |  |  |  |  |
|  | IC/IEG/TFD<br>DECEMBER 1984   |  |  |  |  |
| PROBABLE REACTIVE ARMOR ON T-80 TANK KHARKOV TANK AND VEHICLE TEST FACILITY, USSR (SWN)  | 25X1  |  |  |  |  |
| 1. SIGNIFICANCE: A T-80 TANK WITH PROBABLE BLOCKS OF REACTIVE ARMOR WAS OBSERVED AT THE KHARKOV TANK AND VEHICLE TEST ON IMAGERY OF THIS IS THE FIRST SIGHTING (WITH OR WITHOUT REACTIVE ARMOR) IN THE KHARKOV AREA. TESTING OF A T-80 TANK WITH PROBABLE REACTIVE ARMOR AT SUGGESTS THAT KHARKOV TANK AND LOCOMOTIVE PLANT MALYSHED IS INVOLVED IN THE T-80 PROGRAM AND WAS INVOLVED IN THE TESTING OF THE T-64B WITH REACTIVE ARMOR  | FACILITY OF A T-80 25X1 THE KHARKOV V TS ALSO 25X1                              |  |  |  |  |
| 2. REMARKS: THE TANK IS LONG OVERALL, WHICH PR THE POSSIBILITY THAT IT IS A LONG T-64 SERIES THE PROBABLE REACTIVE ARMOR WAS APPLIED TO THE TURRET F SIDES, PART OF THE TURRET ROOF, AND UPPER GLACIS PLATE DECK). THE T-80 WITH PROBABLE REACTIVE ARMOR APPEARED UNDERGOING TESTING/MAINTENANCE AT A SMALL INSPECTION AR THE TANK RESEARCH AND DEVELOPMENT (R AND D)/TANK GUN FI AT THE TEST FACILITY. THIS FACILITY, 6 NM SOUTH OF THE TANK PLANT, IS PRIMARILY USED TO PERFORM MILITARY ACCEP LIMITED R AND D TESTING ON THE T-64 SERIES OF TANKS, IN THE T-64B, WHICH ARE PRODUCED AT THE NEARBY TANK PLANT. | TANK. 25X1 FRONT, (FRONT TO BE REA NEAR RING AREA E KHARKOV PTANCE AND ICLUDING |  |  |  |  |
| A LESS LIKELY EXPLANATION FOR THE UNUSUAL APPEARANCE OF AT KHARKOV IS THAT CANVAS OR NETTING IS DRAPED OVER THE AND SIDES OF THE TURRET AS WELL AS THE GLACIS. NORMALL HOWEVER, TANKS SEEN AT THE TEST FACILITY, ESPECIALLY THON THE TRACK, DO NOT HAVE CANVAS ON THEM. (SWN)  THE FIRST SIGHTING OF A SOVIET TANK (A T-64B) WITH REACARMOR WAS AT BERNAU BKS/HO ARTY 244  THE TANKS AT BERNAU WERE IN A SOVIET MOTORIZED RIFLE REVEHICLE PARK. SEVERAL CHANGES HAD BEEN MADE TO THE T-60RDER TO ACCOMMODATE THE REACTIVE ARMOR. THESE CHANGES THE REMOVAL OF THE V-SHAPED WAVE DEFLECTOR ON THE GLACI           | E FRONT LY, HOSE OUT  ETIVE 25X1 EGIMENT 64B IN 6 INCLUDE                       |  |  |  |  |
| These notes have been prepared for briefing purposes only and should not be used for detailed analytical work. Their use should be restricted to the particular briefing board(s) they were prepared for and must be considered valid only for the reporting period as indicated by the date of issue.   | 25X1  |  |  |  |  |
| WARNING NOTICE INTELLIGENCE SOURCES OR METHODS INVOLVED  | 25 <b>X</b> 1   |  |  |  |  |

Sanitized Copy Approved for Release 2010/07/21 : CIA-RDP85T00060R000300110001-9

| <br>SECRET |  |
|------------|--|
|            |  |
|            |  |

25X1

## (c) NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER

| Page $\frac{2}{}$ of $\frac{3}{}$ | Attachment to | Z-17249/84      |
|-----------------------------------|---------------|-----------------|
| Copy                              |               | NPIC/IEG/TFD    |
|                                   |               | 6 DECEMBER 1984 |

RELOCATION OF ALL GRENADE LAUNCHERS TO THE REAR AND LEFT SIDE OF THE TURRET, AND THE RELOCATION OF SEVERAL OF THE EQUIPMENT BOXES ON THE TURRET. (SWN)

A SIMILARITY EXISTS BETWEEN THE T-80 AT KHARKOV AND THE REACTIVE ARMOR EQUIPPED T-64B TANKS AT BERNAU. HOWEVER, TWO MODIFICATION FEATURES ON THE T-80 DIFFER FROM THOSE ON THE T-64B. WE CANNOT SEE IF THE GRENADE LAUNCHERS HAVE BEEN RELOCATED. SECONDLY, THE APPLICATION OF THE REACTIVE ARMOR AT KHARKOV DIFFERS SLIGHTLY FROM THAT AT BERNAU. THE T-80 APPEARS TO HAVE MORE REACTIVE ARMOR PLACED ON THE RIGHT SIDE OF THE TURRET NEAR THE COMMANDER'S CUPOLA. (SWN)

ANALYST'S COMMENTS -- THE T-80 TANK WITH PROBABLE REACTIVE ARMOR WAS AT KHARKOV FOR TESTING. MOST LIKELY, REACTIVE ARMOR WILL EVENTUALLY BE SEEN ON THE T-80 . THE 25X1 MODIFICATIONS TO THE T-64B AND T-80, INCLUDING THE REMOVAL OF THE V-SHAPED WAVE DEFLECTOR, THE WELDING OF STUDS TO HOLD THE REACTIVE ARMOR, AND THE RELOCATION OF GRENADE LAUNCHERS AND EQUIPMENT BOXES ARE PROBABLY DONE AT THE TANK PLANT WHEREAS THE INSTALLATION OF THE REACTIVE ARMOR ON THE T-80 WILL PROBABLY BE DONE IN GARRISON AS IT IS ON THE T-64B TANK. SHIPPING BOXES FOR THE REACTIVE ARMOR WERE SEEN AT BERNAU ADJACENT TO T-64B TANKS THAT HAD BEEN MODIFIED TO ACCEPT REACTIVE ARMOR. (SWN)

NO OTHER TANKS EQUIPPED WITH REACTIVE ARMOR HAVE BEEN IDENTIFIED AT KHARKOV ON A REVIEW OF IMAGERY. FURTHER SIGHTINGS OF T-80 AT KHARKOV WILL BE NECESSARY TO CONFIRM THE EXTENT OF THIS PLANT'S INVOLVMENT IN THE T-80 PROGRAM. REACTIVE ARMOR EQUIPPED T-80 TANKS HAVE NOT BEEN SEEN AT OMSK TANK PLANT VOROSHILOV 174 (BE THE ONLY CONFIRMED PRODUCER OF T-80 TANKS, OR AT ITS NEARBY TEST FACILITY. WITH REACTIVE ARMOR CONFIRMED ON THE T-64B AND NOW PROBABLY ON THE T-80, THE SOVIETS HAVE APPARENTLY DECIDED THAT REACTIVE ARMOR WILL BE AN IMPORTANT FACTOR IN INCREASING THE SURVIVABILITY OF THEIR TANK FORCE. (SWN)

ADDITIONALLY, THE DRAPING OF CANVAS OVER THE GUN TUBES AND PROBABLY THE FRONT OF MOST OF THE TANKS AT THE SHIPPING YARD OF THE KHARKOV TANK PLANT SINCE MAY 1983 (NPIC IAC 461 FOR 25 OCTOBER 1983) COULD BE RELATED TO THE REACTIVE ARMOR PROGRAM. T-64B TANKS MIGHT HAVE BEEN MODIFIED TO ACCEPT REACTIVE ARMOR AS

These notes have been prepared for briefing purposes only and should not be used for detailed analytical work. Their use should be restricted to the particular briefing board(s) they were prepared for and must be considered valid only for the reporting period as indicated by the date of issue.

25X1

25X1

WARNING NOTICE INTELLIGENCE SOURCES OR METHODS INVOLVED **SECRET** 

25X1

**SECRET** 

|          |                 |        |  |                   |                            | 25 <b>X</b> 1 |
|----------|-----------------|--------|--|-------------------|----------------------------|---------------|
|          |                 | (c) NA | TIONAL PHOTOGRAPHIC INTERPRETA                               | TION CENTER       | 1                          |               |
|          | Page _3 _ of _3 | 3      |  | Attachment to     | Z-17249/84                 |               |
|          | Сору            |        |  |                   | NPIC/IEG/TFI<br>6 DECEMBER |               |
|          | PREVENT TI      | HE OĖ  | WITH THIS CONCEALMENT EFFOR SERVATION OF THESE CHANGES,      | <b>ESPECIALLY</b> | THE REMOVAL                |               |
|          | SHIPPING        |        | FLECTOR OR THE PRESENCE OF D<br>T-64 SERIES AND THE<br>(SWN) | T-80) I           |                            | 25X1          |
| <b>.</b> |                 |        | COORDINATES 49-53-20N 036-2                                  | 0-05E (S)         |                            | 25 <b>X</b> 1 |
|          | ANALYST:        |        | (U)  |                   |                            | 25X1          |

These notes have been prepared for briefing purposes only and should not be used for detailed analytical work. Their use should be restricted to the particular briefing board(s) they were prepared for and must be considered valid only for the reporting period as indicated by the date of issue.

25X1

WARNING NOTICE INTELLIGENCE SOURCES OR METHODS INVOLVED

4.

ANALYST:

SECRET